

Appendix 7

EARL'S COURT STATION WARWICK ROAD ENTRANCE REFURBISHMENT POTENTIAL WORKS

Potential external works

- low pressure clean to brickwork;
- repair render to frieze and repaint;
- cladding over name frieze;
- backlit new entrance banner;
- new wayfinding signs;
- remove LUL roundel;
- replace doors with powder coated units;
- new advertising poster units with back-lighting;
- replace railings with perforated metal cladding to sides of building;
- new perforated cladding and framework hung from existing structure;
- new canopy;
- external lighting;

Potential internal ticket hall works

- metal cladding system to brick panels;
- powder coated Al frieze with backlit sign;
- new wayfinding signs;
- integrated cable management system;
- remove glazed panels and replace with Al pc laminated glazed panels;
- extra over for louvres to top of last;
- take up old floor and provide new terrazzo;
- complete new retail units to replace old existing;
- strip and replace soffit and replace all light fittings;

Potential internal passageway works

- line walls with Al pc panels;
- replace advertising units under glazing;
- replace all glazing with new Al pc laminated glazed panels;
- take up old floor and provide new terrazzo;
- pc Al suspended ceiling system with integral lighting and CMS;

Potential other works

- tactiles to stair treads and nosings, visual highlights to obstructions etc;
- upgrades to fire alarms to meet current regulations;
- amendments to lighting to increase lux levels;

- glazed powder coated Al cladding to station control room (behind perforated cladding).